

PRESSURE TRANSIENT IN PIPE NETWORKS, SIMULATION AND ANALYSIS

Fadel Salem Gseaa and Elhadi Ibrahim Dekam

Mechanical and Industrial Engineering Department
Alfateh University, Tripoli, Libya
E-Mails: fadhil1223@yahoo.com ; eidekam@hotmail.com

المخلص

تم في هذه الدراسة بحث الضغط العابر في شبكة أنابيب والنتائج من مصادر مختلفة. وتم استخدام برنامجي AFT Impulse و Hammer لتحليل سلوك التدفق العابر، وكانت النتائج المتحصل عليها من البرنامجين متوافقة جدا مع بعضها البعض وتم مقارنتها مع نتائج منشورة لنفس الحالات.

وفي الحالة التي تم دراستها، وجد ان خواص مكونات الشبكة كنوع الصمام وطريقة قفله ونوع مادة الانابيب وايضا نوعية معامل الاحتكاك المستخدم ومعدات الحماية من الضغط العابر لها تأثير كبير على مقدار الضغط العابر في الشبكة. بينت النتائج ان استعمال صمام خانق ذو قرص بدلاً من الصمام البوابي قلل اعلى ضغط عابر بمقدار 33 %، وقفل الصمام على مرحلتين بدلاً من قفله فجائيا بحيث يكون زمن القفل قصير في المرحلة الأولى قلل الضغط العابر الأعلى المتولد بمقدار 41 % . كان لإستخدام أنابيب "البي في سي" ذات معامل المرونة المنخفض بدلاً من الأنابيب المصنوعة من الحديد المطيلى قلل الضغط العابر الاعلى بمقدار 30 % ومن ناحية أخرى زاد الضغط العابر الأدنى فتم بالتالي تجنب فصل عمود السائل. أثبتت النتائج المتحصل عليها من الدراسة أن إستخدام معامل إحتكاك غير مستقر يؤدي إلى ضغط متذبذب اقل منه في حالة إستخدام معامل الإحتكاك المستقر.

بالنسبة لوسائل حماية الشبكة، وجد ان تركيب غرفة هوائية عند مسافة قريبة من مخرج المضخة يقلل من تذبذب الضغط كمثّل ما يحدث عند إستعمال مضخة ذات سرعة متغيرة بسبب موقع المضخة المرتفع نسبيا في الشبكة.

ABSTRACT

The transient pressure in a pipe network with different sources of transient is investigated in this study. Hammer and AFT Impulse softwares were employed to accomplish the transient flow behavior analysis. The outputs from both softwares are agreed very well and they compared with the available published results for the same conditions.

In a case study, the characteristics of the network components such as valve type, valve closing rate, pipe material, friction model and surge protection device, are found to be highly affecting the amount of pressure surge in the network. The results showed that using butterfly valves in such case lowered the maximum transient pressure head by 33% compared to that when gate valves are employed. Using two stage valve closing rates with short duration time of the first stage lowered the maximum pressure head by 41% relative to that for sudden closure. Using pipes with low elasticity, PVC pipes, decreases the maximum pressure by 30%, however, the minimum pressure is increased where the column separation is avoided.

The studied case results confirm that using unsteady frictional model leads to less oscillated pressure compared to steady frictional model. Installation of an air chamber at

a short distance from the pump discharge reduces the oscillation of pressure as that produced due to using variable speed pump when the static head of the pump is relatively low due to higher pump elevation.

Key Words: Transient flow, water hammer, surge protection, network flow analysis.

INTRODUCTION

Transient pressures in pipe networks commonly initiate due to sudden changes in valve settings (accidental or planned; manual or automatic), starting or stopping of either supply or booster pumps, changes in the demand conditions, including starting or arresting fire flows, sudden change in reservoir level, changes in transmission conditions, such as when a pipe breaks or buckles, and sudden release of air from relief valves at high elevation points in the network or during filling or flushing operations [3].

In such cases, the kinetic energy of the fluid is converted to pressure energy transmitted as pressure waves that travel with speed of sound along the system pipes. This phenomena is famous and known as water hammer phenomena. This phenomenon must be taken into consideration when evaluating and designing hydraulic systems. The excessive pressure rise can cause rupture of pipes, however, the low pressures leading to the possibility of column separation. Therefore, the pipe network must be designed to avoid and/or withstand the excessive high and low pressures. A number of sited references analyze a specified transient flow control volume that leads to the desired partial differential governing equations.

In order to model the water hammer phenomenon in a network, it is required to solve a set of continuity and momentum equations. The continuity and momentum equations form a set of non-linear, hyperbolic, partial differential equations which is not easy to deal with [2].

Usually, to solve such transient equations, numerical methods are employed with the required initial and boundary conditions. For a water distribution system, there are many more parameters needed for solving the water hammer problem. In a water distribution system, every branch of the system requires an additional boundary condition. External boundary conditions take the form of a driving head, or a flow leaving the system. Internal boundary conditions arise in the form of nodal continuity, energy loss between points, head across valves, pumps, and more.

The complexity of the problem requires the use of modeling software that mostly uses the method of characteristics (MOC). The MOC is the most widely used and tested approach; it has the best accuracy of any of the finite difference methods and can handle very complex systems [1]. Computer modeling of water hammer in pipe systems provides a tool for simulation of water hammer events, and thus provides better understanding of the pressure wave behavior.

HISTORY OF COMPUTER MODELS

Cesario (1991) discusses a number of different ways that network computer models are used in planning, engineering, operations, and management of water utilities. These models include network models, pump scheduling, tank turnover analysis, energy

optimization, operator training, water quality analysis, fire-fighting flow studies, and others [3].

The groundwork for computer modeling of distribution systems was laid by the numerical method developed by Hardy Cross in the 1930s for analyzing looped pipe networks, Cross, 1936. The first mainframe programs for pipe-network analysis that appeared in the 1960s were based on this method, Adams, 1961, but these were soon replaced with codes that use the more powerful Newton-Raphson method for solving the nonlinear equations of pipe flow, Dillingham, 1967; Martin and Peters, 1963; Shamir and Howard, 1968 [3].

The 1970s saw a number of new advancements in network solution techniques. New, more powerful solution algorithms were discovered, Epp and Fowler, 1970; Hamam and Brameller, 1971; Wood and Charles, 1972, techniques for modeling such non pipe elements as pumps and valves were developed, Chandrashekar, 1980; Jeppson and Davis, 1976. Ways were found to implement the solution algorithms more efficiently, Chandrashekar and Stewart, 1975; Gay et al., 1978. The extension from single-time-period to multitime-(or extended) period analysis was made, Rao and Bree, 1977 [3].

The 1980s were marked by the migration of mainframe codes to personal desktop computers, Charles Howard and Associates; 1984; Wood, 1980. They also saw the addition of water-quality modeling to network analysis packages, Clark et al., 1988; Kroon, 1990. Benjamin Wylie and Victor Streeter, 1993, combined the method of characteristics with computer modeling. The field of fluid transients is still rapidly evolving worldwide, Brunone et al., 2000; Koelle and Luvizotto, 1996; Filion and Karney, 2002; Hamam and McCorquodale, 1982; Savic and Walters, 1995; Walski and Lutes, 1994; Wu and Simpson, 2000 [3]. In the 1990s, the emphasis has been on graphical user interfaces, Rossman, 1993, and the integration with CAD programs and water utility databases, Haestad Methods, 1998.

EMPLOYED SOFTWARES

In ref [2], a number of different fluid flow softwares are considered, and hence evaluated, in order to select and employ the appropriate software for calculating and simulating the transient pressure wave produced by water hammer phenomena in water transport networks under different geometrical and operational conditions. Among of the considered softwares are; Bentley Hammer, AFT Impulse, Hytran, Hi-Trans and UPSURGE for transient flows and EPANET, pipe flow, fluid flow3 for steady flow analysis. These softwares are evaluated individually under different tasks. Two of the softwares were selected to use for transient flows; one is AFT Impulse, and the other is Bentley HAMMER. The steady state solution was also tested with EPANET 2 software [2].

EPANET 2

EPANET is a computer program that performs steady state and extended period simulation (EPS) of hydraulic and water quality behavior within pressurized pipe networks. It was developed in National risk management research laboratory under the U.S. Environmental Protection Agency. The program can be used for many different kinds of applications in distribution systems analysis. Sampling program design,

hydraulic model calibration, chlorine residual analysis, and consumer exposure assessment are some examples [5].

AFT Impulse

It is powerful water hammer modeling tool from Applied Flow Technology, it is supplied with steady state solution engine which solves for system initial condition, these results used automatically to initialize the transient model which solved by method of characteristics.

HAMMER

Bentley HAMMER is an advanced numerical simulator of hydraulic transient phenomena in water, wastewater, industrial, and mining systems. It simplifies data entry and allows the users to focus on visualizing, improving, and delivering results quickly and professionally. Bentley HAMMER can handle different fluids and /or systems, analyze drinking water systems, sewage force-mains, fire protection systems, well pumps, and raw-water transmission lines [3].

Pressure Wave Speed

The pressure wave speed along the transient flow passage is one of the important parameters that determine the behavior of the studied transient flow. Referring to a number of references and according to specific assumptions; fluid and pipe wall are linearly elastic, pipe is full and the flow is one-dimensional, fluid is homogeneous, average velocity is used, and viscous losses similar to steady state. These assumptions are essentially valid for the majority of the time-dependent problems in the majority of water systems.

Referring to the continuity and momentum equations sited else where [1,3], that they are needed to determine the local flow velocity and local static pressure in each segment, the general expression for pressure wave speed, a , can be written as follows:

$$a = \frac{\sqrt{K/\rho}}{\sqrt{1 + \frac{K D}{E e} (C)}}$$

Where:

- a the pressure wave speed
- K the bulk modulus of elasticity of the fluid.
- E Young's modulus of elasticity of the pipe.
- ρ the fluid density.
- D the inner pipe diameter.
- e the thickness of the pipe wall.
- C a function that has different expressions.

The parameter C takes different forms depending on whether the pipe is rigid or flexible, and on the specific pipe fixation method. Accordingly, the wave speed will have different expression for each case, which sited in ref. [1].

Frictional Model

Generally friction losses in the simulation of transient pipe flow are estimated by using formulae derived for steady state flow conditions. This is known as the quasi-steady approximation. Darcy-weisbach friction factor in the governing equations is a steady state friction factor. The head loss during transient flow is equal to the head loss obtained for steady uniform flow with an average velocity equal to the instantaneous transient velocity.

Although this approximation is enough to calculate the maximum pressures in the absence of vapor cavities or column separation, this is not accurate for the prediction of the time history of pressure oscillations and the attenuation of pressure waves. An accurate calculation of the damping effect due to unsteady friction losses is important for long time simulations and for systems having multiple operations. This paper represents both friction models for evaluation and comparison.

Column Separation

The breaking of liquid columns in fully filled pipelines may occur in a water-hammer event when the pressure in a pipeline drops to the vapor pressure at specific locations such as closed ends, high points or knees. The liquid columns are separated by a vapor cavity that grows and diminishes according to the dynamics of the system. The collision of two liquid columns, or of one liquid column with a closed end, may cause a large and nearly instantaneous rise in pressure. This pressure rise travels through the entire pipeline and forms a severe load for hydraulic machinery, individual pipes and supporting structures. This column separation could be seen clearly at the discharge side of the stopped pump or at the downstream of a sudden closed valve.

CASE STUDY

More than 15 different networks are selected from different references, where transient analysis is made by AFT Impulse and Hammer softwares. The selected networks have different complexity; different sources of transient and different protection devices, the reader is recommended to consult Ref [2]. Here, a special case study is investigated in details.




Figure 1: Case study network layout

The network includes six galvanized iron pipes, three reservoirs, six nodes, an Ingersoll-Dresser 20KKH pump and a gate valve. A sketch of the network is presented in Figure 1. The given data for the pipes, nodes, and reservoirs are shown in Figure 1, the pressure wave speed for all pipes is 2850 ft/s, and gate valve closing rates are listed

in tables 2, 3, and 4. Valve loss coefficient is (K_L); the values of $1/K_L$ are tabulated in table 1. Pump station data and pump characteristics are listed in table 5. Firstly, friction model used is a steady friction model using Darcy-Weisbach equation.

Table 1: Values of ($1/K_L$) as a function of percentage opening.

% open	0	10	20	30	40	50	60	70	80	90	100
$1/K_L$	0	0.0167	0.0313	0.0565	0.1	0.179	0.333	0.635	1.25	2.5	5.27

Table 2: Valve closing rate (I)

Time (sec)	Relative closure (%)
0	0
0.08	100

Table 3: Valve closing rate (II)

Time (sec)	Relative closure (%)
0	0
1	95
20	100

Table 4: Valve closing rate (III)

Time(sec)	Relative closure (%)
0	0
20	50
40	100

Pump station information's

No. of pumps =1
 No. of stages =1
 RPM =1180
 Inertia = 50 lb-ft²

Table 5: Pump characteristics

Q (gpm)	0	2000	3000	4000	4500	5300
Head(ft)	118	92	82	67	52	0
HP	57	68	77	80	76	60

This network experiences a transient flow behavior caused by either a gate valve closure or due to a pump failure. In the case of valve closure, investigation of the effect of valve closing rate, valve type, and pipe material is made, through presenting the local transient pressure head at specific locations. However, in the case of pump failure, the effect of installing variable speed pump rather than constant speed pump, installing air chamber(s) and/or surge tank(s), and increasing the inertia of the pump are investigated.

Many numerical and graphical results for modelling and simulating the transient pressure for this case study have been obtained. Here, only a limited number of such results is presented, and for more information, the reader may refer to Ref. [2].

RESULTS AND DISCUSSIONS

Effect of Valve Closing Rates

Figure (2) shows the transient pressure head, flow rate variation and cavity volume at upstream end of the valve, due to instantaneous valve closing rate (I), the pressure head increased sharply to 659 ft during the first 2.3 seconds, and dropped down to -34.5

ft at $t = 7.69$ sec, where the pipe is evacuated leading to a column separation. The cavity collapsed at $t = 8.4$ sec. The pressure head oscillates with decreasing rate until reaches steady state pressure distribution.




Figure 2: Transient history (Pressure, Flow & cavity volume) at the upstream end of the valve using closing rate (I).

Figure (3) represents the transient pressure head, and flow rate variations with time at the upstream end of pipe 5 (at junction 3), with valve closing rate (I). At this location, the pressure head is initially at steady state head (424 ft) at $t = 0$. When the pressure wave arrived to the junction, the pressure head is increased to 536 ft at a time of 1.16 sec. It continues to increase to a maximum value of 544 ft at $t = 3.4$ sec. After this maximum value, the pressure continues to oscillate with decreasing rate until it reaches the steady state pressure head.

Figure (4) represents the local pressure head variation with time at the upstream end of the gate valve (P5: TCV-1), due to valve closure with rates I, II, and III. The figure shows that using two stage valve closing rate generate lower transient pressure head compared with instantaneous or linear closing rate. Using two stage closing rate reduces the maximum transient pressure by 41%.




Figure 3: Transient history (Pressure, Flow & cavity volume) at the upstream end of Pipe 5 (junction 3), using closing rate (I).

Figure (5) represents the steady state, minimum and maximum transient pressure heads along the pipe path starting from throttling control valve to reservoir 1 through joints 3 and (1), respectively, (TCV-1 → J-3 → J-1 → R-1), due to valve closing rate (I). The maximum pressure is 815 ft which occurs in pipe (5) at a location $x = 2636.8$ ft (663.2 ft before joint 3). The minimum transient pressure head equals to -34.5 ft that occurs at the upstream end of the valve end at time of 7.6 sec. obviously, the maximum cavity volume occurs at the same point, at the upstream end of the valve.




Figure 4: Effect of valve closing rate on local transient pressure head at the upstream end of the gate valve.




Figure 5: Pressure and cavity volume along path (TCV-1 → J-3 → J-1 → R-1), due to valve closing rate (I)

Figure (6) represents the pressure profile along the pipe path (TCV-1 → J-3 → J-1 → R-1), due to linear valve closing rate (III). The maximum transient pressure head equals to 731.2ft which occurs at a location of $x = 2000$ ft. However the minimum transient pressure head is -16.1 ft occurs at the upstream end of the valve at $t = 47.5$ sec.




Figure 6: Pressure and cavity volume along path (TCV-1 → J-3 → J-1 → R-1), due to valve closing rate (III).

Effect of Valve Type

Figure 7 shows a comparison between the pressure heads and flow rates at the end point of P-5: TCV-1 in case of using gate, butterfly or globe valves, due to valve closing rate (II). It is clear that valve type that used in the system is important in determining transient flow behaviour. Globe valve used ($K_L = 4.1$) cause higher pressures than the other type of valves. In this case, using butterfly valves ($K_L = 0.6$) reduces the maximum pressure by 33%. Numerical values, for comparing the maximum, minimum pressures generated by each valve, are listed in table 6.




Figure 7: Effect of valve type on transient pressure head.

Table 6: Effect of valve type on pressure head generated.

Valve type	Pressure head generated (ft)	
	Maximum	Minimum
Gate	375	131
Butterfly	257.8	182.8
Globe	556.4	117.6

Effect of Pipe Material

One may use pipe material that has low elasticity in order to reduce the induced transient pressure head. Figure (8) shows the effect of using PVC pipes whose $E = 478624.5$ psi, on transient pressure head and column separation at the upstream end of pipe (5) with gate valve closing rate (I). The maximum transient pressure decreased by 30% from 660.6 ft to 459.3 ft, and the minimum pressure increased 425% from -32.8 ft to 106.6 ft, thus the column separation is avoided when PVC pipes were used in such case.

Installing a Variable Speed Pump

In general the effect of water hammer phenomena can be reduced by making the network absorbs the extreme pressure fluctuations. For the network presented in Figure (9), two surge protection treatments are considered; installing a variable speed pump or installing an air chamber.

Figures (9) and (10) show the effect of using surge protection devices, a variable speed pump is installed instead of constant speed one at the same location of the indicated system. Here, the speed of the pump is taken as to be reduced linearly during the first

25 sec; this effect is represented by the local transient pressure head due to the pump failure at the pump discharge side and at the downstream end of pipe 6.




Figure 8: Effect of using PVC pipes on the local pressure head variations and cavity volume at the end of pipe 5 with closing valve rate (I).




Figure 9: Effect of protection device on local transient pressure at pump discharge side

Installing an Air Chamber

Figures (9) and (10) show also the effect of installing an air chamber on the local transient pressure due to pump failure. The air chamber is installed at 10 ft downstream of the pump discharge with the following specifications: initial air volume = 100 ft³, initial water volume = 50ft³, initial HGL = 4225.48 ft, and the diameter of tank inlet orifice = 7 in., and the gas specific heat ratio = 1.2.

The figures show that using the variable speed pump or the air chamber specified, is efficient in controlling the oscillation frequency of the pressure and flow. In this case, one may notice that the pressure difference and oscillation frequency of the pressure are low due to the location of the pump in the network, where the pump elevation is relatively high in the network.




Figure 10: Effect of protection device on the local transient pressure at downstream end of pipe 6.

Employing unsteady friction model

Figure (11) represents the pressure head variation at the end point P-5: TCV-1, due to instantaneous valve closure; closing rate (I), in both cases of using steady and unsteady friction factor. Using unsteady friction factor generate lower pressures than pressures generated by using steady friction factor which leads to shorter time to reach steady state.




Figure 11: Effect of friction model used on transient pressure, at upstream of the valve.

8. CONCLUSIONS

From the previous case results, the following conclusions and recommendations can be summarized in the following points:

1. Study of transient behaviour becomes easier with modern softwares, such as Hammer and AFT Impulse. The output results from both softwares are confirmed to have high accuracy; thus they are recommended to use for solving transient problems.
2. There are many advantages in Hammer software: It is easy to use, but it needs a long time training to get accurate results. Input data, pipes, nodes, reservoirs, surge tank(s), air chamber(s), and necessary data for transient source such as valve and pump characteristics must be modeled accurately.
3. Valve closing rate is the key for the behavior of the transient flow; it could be dangerous for sudden closure or mild for slow closure, therefore two stage closing rate is recommended in pipe networks.
4. Pump, pipe, and valve characteristics and type, play an important role in transient flow generation profile which leads to what type of protection devices should be employed. Transient pressure effects can be avoided or reduced by selecting appropriate network components and applying proper operations by trained operators.

5. Effect of friction is important in transient analysis, using unsteady friction model provide higher friction factor than using steady friction model, which tends to have low oscillation frequency for pressure along transient path.
6. While modern studies of water hammer phenomena needs good knowledge in fluid mechanics and mechanical devices related to water transport systems; selecting surge protection mechanisms needs the previous knowledge of water hammer phenomena and long time experience with such systems.

NOMENCLATURE

CAV = Combination air valve.
El. = Elevation.
HGL = Hydraulic grade line.
HP = Horse Power.
PMP = Pump.
Q = Volume flow rate.
SAV = Surge Anticipator valve.
TCV = Throttle control valve.
SRV = Surge Relief Valve.
VSP = Variable speed pump.
VSPB = Variable speed pump Battery.

REFERENCES

- [1] **Bruce E. Larock, Roland W. Jeppson, Gary Z. Watters**, “Hydraulics of Pipeline Systems”, CRC Press, 2000.
- [2] **Fadel S. Gasiaa**. “Pressure transient in networks, simulation and analysis”, M.Sc. thesis, Al-Fateh University, 2009.
- [3] “Bentley HAMMER V8 XM Edition User’s Guide”, Bentley Systems, Incorporated and Haestad Methods Solutions Center, 2007.
- [4] **Haestad Methods, Thomas M. Walaski, et al**, “Advanced Water Distribution Modeling and Management”, 1st edition, Haestad Press, 2004.
- [5] **Lewis A. Rossman**, “EPANET 2 users manual”, US Environmental Protection Agency, September 2000.